

**Name of work : Maintenance of 500KVA Transformer at Corporate Office, Thimphu****Bill of quantity**

SL.NO	Particulars	Quantity	Unit	Rate		Amount
				Figure	Word	
1	Cleaning, draining and changing of transformer oil(Top-up)	120	Ltrs			
2	BDV Transformer oil testing	1	each			
3	Maintenance and rectification of leakages	1	each			
4	Testing of Earthing	1	each			
5	Current and resistance(IR) Testing	1	each			
6	Changing of gasket including all accessories complete set	2	each			
7	Changing and replacement of Silicagel	2	kg			
8	Opening, fitting and cleaning all parts of transformer	1	each			
9	Providing and fitting of pressure relieve from Transformer and Buchholz relay.	1	each			
<b>Total amount in Nu.</b>						
<b>Rebate offer</b>						
<b>Final amount after rebate in Nu.</b>						